

Factory Installed Mobile Wheel Kit & Detachable Handle For Truck Scissor Dock Lift Units

MODEL WL-WK

Loading Dock Equipment / Premium Truck Scissor Dock Lifts

PRODUCT OVERVIEW

Optional mobile wheel kit system includes casters and a detachable handle.

KEY FEATURES

- Optional mobile wheel kit includes a dolly jack for ideal operation
- Ideal for the scissor dock lift for maximum efficiency
- Features durable construction for added strength and long life
- Use in industrial applications for optimal results



CORE PRODUCT DATA

ASSEMBLED WEIGHT
32 lbs

ASSEMBLED SIZE
4" W x 6" L x 4" H

SHIP WEIGHT
32 lbs

PACKAGE 1 SIZE
4" W x 6" D x 4" H

COLOR / FINISH
Yellow

FREIGHT TYPE
LTL Palletized

AVAILABILITY Available

QUICKSHIP: --

Products are sold through Vestil distributor partners. Contact a distributor for current pricing and ordering.

PRODUCT SPECIFICATIONS

Uniform Capacity (lb.)	6000
Size	Fabricated to Fit Unit
Handle Width (in.)	23-3/4
Handle Height (in.)	65-1/16
Swivel Caster (qty.)	2
Swivel Caster Diameter (in.)	4
Swivel Caster Width (in.)	2-1/2
Rigid Caster (qty.)	2
Rigid Caster Diameter (in.)	4
Rigid Caster Width (in.)	2
Caster Material	Glass-Filled Nylon
(4) Clevis Pin	3/8 x 4-5/8
quantity Hairpin clip	4
quantity "bulldog" Couplers	8

PRODUCT & SHIPPING REFERENCE

Shipping Point: Angola, IN 46703

Warranty:

90 Days

AVAILABLE PRODUCT RESOURCES



SCAN FOR CURRENT PRODUCT DATA

Live product page: <https://www.vestil.com/product.php?FID=1>